

15-065-02711-00-02

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970
CONSERVATION DIVISION
Wichita, Kansas
5-27-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address Box #553, Russell, Kansas.

Lease Name Holley LKC Unit-North Well No. 301

Location CSW-SE-NE Sec. 29 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3920'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 11:00 AM Day 23 Month 5 Year 1970

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated.
3910'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3690'. Hole in casing @ 3295'.

Pushed plug to 3200' and built sand bridge to ~~32~~ 3175' then set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 12 sacks gel then 100 Sx. cement from 1125' to 800' then 14 sacks gel from 800' to 240' and followed with 20 Sx. cement from 240' to 180' then 4 sacks gel from 180' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-350#. Final shut-in pressure 200#. (Mudding and cementing operations by Halliburton)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 5/28/70
INV. NO. 1959-W