

15-065-02712-00-01

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 14 1974  
2-14-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Cities Service Oil Company,

Complete Address 710 Sutton Place, Wichita, Kansas.

Lease Name Holly LKC Unit North Well No. 302-W

Location NE-SE-NE Sec. 29 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3900'

Abandoned Oil Well X Gas Well        Input Well X SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 5:30 PM Day 11 Month 2 Year 1974

The above well was plugged as follows:

195'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3900'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to 3770', top per-  
forations from 3742' to 3744'.

Sanded well back to 3720' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(717') and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed  
with 110 Cu. Ft. cement from 1125' to 800' then 15 sacks gel from 800' to 200' and  
followed with 30 Cu. Ft. cement from 200' to 125' then 2 sacks gel from 125' to 45'  
and finally 10 Cu. Ft. cement from 45' to bottom of cellar. Maximum pump-in pressure  
-300#. Final Shut-in pressure-100#. (Mudding & cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Pichler  
Well Plugging Supervisor

INVOICED

DATE 2/18/74  
INV. NO. 8573-W