

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED

MAY 20 1971

CONSERVATION DIVISION
Wichita, Kansas

5-20-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address P. O. Box #922, Great Bend, Kansas.

Lease Name T. L. Smith Well No. 6

Location NE-SW-SE Sec. 30 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3960'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:00 AM Day 15 Month 5 Year 1971

The above well was plugged as follows:

318'--20 3/4" Surface casing, cement circulated with 210 Sx.

3959'--7" OD Production casing cemented on bottom with 150 Sx. Well plugged back to 3955'. Top perforations from 3940' to 3944'.

Sanded well back to 3930' and set 6 Sx. cement with dump bailer. Pulled 7" casing (2815') and squeezed well initially with 5 sacks hulls and 12 sacks gel then 130 Sx. cement from 1175' to 850' then 16 sacks gel from 850' to 330' and followed with 30 Sx. cement from 330' to 250' then 7 sacks gel from 250' to 30' and finally 15 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-200#. Final shut-in pressure-150#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5-20-71

INV. NO. 3726-W