



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

FEB 25 1974
2-25-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 KSR&T Building, Wichita, Kansas.

Lease Name Holly Unit Well No. 2-2

Location SW-SE-SW Sec. 30 Twp. 8 Rge. (E) (W) 2 1/2

County Graham Total Depth 3948'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Halliburton Services,

Address Box "D", Hill City, Kansas. License No. _____

Operation Completed: Hour 4:00 PM Day 18 Month 2 Year 1974

The above well was plugged as follows:

325'--10 3/4" Surface casing, cement circulated with 250 Sx.
394 1/2'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool set @ 2180'
with Chem-Pak circulated to surface. No plug back indicated. Top perforations from
3925' to 3928'.

Sanded well back to 3900' and set 6 Sx. cement with dump bailer. Pulled 7" casing
(2525') and squeezed well initially with 7 sacks hulls and 20 sacks gel and followed
with 83 Sx. Halliburton Lite Cement from 1250' to 900' then 20 sacks gel from 900' to
350' and followed with 27 Sx. cement from 350' to 250' then 10 sacks gel from 250' to
25' and finally 10 Sx. cement from 25' to cellar. Max. Pressure-400#, FSIP-300#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Fickels*
Well Plugging Supervisor

DATE 2/27/74
INV. NO. 8628-W