

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
FEB 25 1974
2-25-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum Management, Incorporated,
Complete Address 1515 KSEA T Building, Wichita, Kansas.
Lease Name Holly Unit Well No. 2-3
Location NE-SW-SW Sec. 30 Twp. 8 Rge. (E) (W) 2h
County Graham Total Depth 3984'
Abandoned Oil Well Gas Well Input Well X SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Halliburton Services,
Address Drawer "D", Hill City, Kansas. License No.
Operation Completed: Hour 1:30 PM Day 18 Month 2 Year 1974

The above well was plugged as follows:

318 ^{KCC ZAP} 210'--10 3/4" Surface casing, cement circulated with 250 Sx.
3983'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool set @ 2212'
with Black Magic circulated to surface. No plug-back indicated. Top perforations
from 3959' to 3964'.

Sanded well back to 3940' and set 6 Sx. cement with dump bailer. Pulled 7" casing
and squeezed well initially with 7 sacks hulls and 20 sacks gel and followed with
83 Sx. Halliburton Lite Cement from 1250' to 900' then 20 sacks gel from 900' to 350'
and followed with 27 Sx. cement from 350' to 250' then 10 sacks gel from 250' to 25'
and finally 10 Sx. cement from 25' to bottom of cellar. Max. Pressure-200#, FSIP-75#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 2/27/74
INV. NO. 8629-W