

15-065-02716-00 00

Form CP-3
Rev. 6-4-68

KANSAS

2

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1971
CONSERVATION DIVISION
Wichita, Kansas
5-20-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,
Complete Address P. O. Box #922, Great Bend, Kansas.
Lease Name T. L. Smith, Holley Unit Well No. 4
Location NE-SE-SW Sec. 30 Twp. 8 Rge. (E) (W) 24
County Graham Total Depth 3978'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 11:30 AM Day 15 Month 5 Year 1971

The above well was plugged as follows:

318'--10 3/4" Surface casing, cement circulated with 210 Sx.
3972'--7" OD Production casing cemented on bottom with 100 Sx. Well Plugged back to
3965'. Top perforations from 3954' to 3959'.

Sanded well back to 3940' and set 6 Sx. cement with dump bailer. Pulled 7" casing
(2725') and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed
with 130 Sx. cement from 1175' to 850' then 16 sacks gel from 850' to 330' and foll-
owed with 30 Sx. cement from 330' to 250' then 7 sacks gel from 250' to 30' and finally
15 Sx. cement from 30' to bottom of cellar. Maximum pressure-300#. Final shut-in
Pressure-200#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*
Well Plugging Supervisor

DATE 5-20-71
INV. NO. 3725-W