

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 25 1974  
2-25-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 KSB&T Building, Wichita, Kansas.

Lease Name Holly Unit Well No. 2-5

Location SW-NE-SW Sec. 30 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3985'

Abandoned Oil Well        Gas Well        Input Well X SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Halliburton Services,

Address Drawer "D", Hill City, Kansas. License No.       

Operation Completed: Hour 11:30 AM Day 18 Month 2 Year 1974

The above well was plugged as follows:

318'--10 3/4" Surface casing, cement circulated with 210 Sx.  
3981'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool set @ 2207'  
with Black Magic circulated to surface. Well plugged back to 3975'. Top perforations  
from 3961' to 3964'.

Sanded well back to 3950' and set 6 Sx. cement with dump bailer. Pulled 7" casing  
and squeezed well initially with 7 sacks hulls and 20 sacks gel and followed with  
83 Sx. Halliburton Lite cement from 1250' to 900' then 20 sacks gel from 900' to  
350' and followed with 27 Sx. Halliburton Lite cement from 350' to 250' then 10 sacks  
gel from 250' to 25' and finally 10 Sx. cement from 25' to bottom of cellar. Maximum  
pump-in pressure-350#. Final shut-in pressure-50#.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 2/27/74

INV. NO. 8630-4