

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1972  
4-17-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Keith Well No. B-4 Tract #9, Well #4

Location SE-SW-SW Sec. 32 Twp. 8 Rge. (E) (W) 2

County Graham Total Depth 3985'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 7:45 PM Day 15 Month 4 Year 1972

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3985'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to  
3973'. Top of perforations @ 3795'. 5 1/2" casing has been squeezed @ 2550' & 2890'  
with 400 Sx. cement.

Pushed plug to 3750', sanded well back to 3725' and set 5 Sx. cement with dump bailer.  
Pulled 5 1/2" casing (1218') and squeezed well initially with 5 sacks hulls and 7 sacks  
gel. Pressure built to 850#, started cement, pumped in 150 Cu. Ft. from 450' to bottom  
of cellar. Maximum pump-in pressure--850#. Final shut-in pressure--75#. Checked well  
4/14/72 found top of cement 5' below bottom of cellar. (Mudding & cementing by Halli-  
burton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 4/17/72  
INV. NO. 5567-w