

KANSAS

RP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address P. O. Box #922, Great Bend, Kansas.

Lease Name Keith Well No. B-5

Location CS/2-NW-NW Sec. 32 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3970'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:30 PM Day 15 Month 5 Year 1971

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 175 Sx.

3969'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3939'. Top perforations from 3920' to 3924'.

Sanded well back to 3900' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 14 sacks gel and followed with 100 Sx. cement from 1175' to 850' then 13 sacks gel from 850' to 225' and followed with 25 Sx. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-200#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 5-20-71
INV. NO. 3724-W