

15-065-02213-00-01

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company.

Complete Address Box #553, Russell, Kansas.

Lease Name Holley IKC Unit Well No. ~~201-11~~ 101W ^{KCC} _{TAP}

Location NE-SE-NW Sec. 33 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 4010'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated.

Address Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 2:45 PM Day 24 Month 6 Year 1969

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated..
4004'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @
3928'.

Sanded well back to 3900' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well with initially 5 sacks hulls and 10 sacks gel and followed with 100
Sx. cement from 1225' to 900' then 16 sacks gel from 900' to 260' and followed with
25 Sx. cement from 260' to 185' then 4 sacks gel from 185' to 25' and finally 10 Sx.
cement from 25' to surface. (Mudding and cementing by Halliburton).

I hereby certify that the ~~state well~~ ^{STATE WELL} was plugged as herein stated.

INVOICED

JUL 1 1969

Signed:

M. S. D. Nichols

Well Plugging Supervisor

DATE 7-1-69

CONSERVATION DIVISION
Wichita, Kansas

7/1/69

INV. NO. 23-W