

02762  
15-005-02972-60-21

KANSAS

Form CP-3  
Rev. 6-26-62

R.

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
6/27/68

Operator's Full Name Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name Holley LKC Unit Well No. 102-W

Location S/2-SW-NW Sec. 33 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 4025

Abandoned Oil Well      Gas Well      Input Well X SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Halliburton Services,

Address: Box #296, Hill City, Kansas. License No.     

Operation Completed: Hour 3:30 PM Day 24 Month 6 Year 1968

The Above well was plugged as follows:

179'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
4025'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 4006'.  
Injection zones from 3948 to 3953 and from 3966' to 3970'. 5 1/2" squeezed in Cedar Hills  
with 225 Sx. cement and 227 Sx. cement. Ran 2" tubing to bottom and displaced 20 Sx.  
cement thru Tubing from 4006' to 3846'. Pulled tubing to 3846 and displaced 20 Sx. gel  
thru tubing from 3846' to 1800'. Pulled tubing to 1800' and displaced 125 Sx. cement  
thru tubing from 1800' to 800'. Pulled tubing to 800' and displaced 8 Sx. gel thru  
tubing from 800' to 40' and finally 5 Sx. cement from 40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

INVOICED

Signed: M. L. Diebold  
Well Plugging Supervisor

DATE 6-27-68

INV. NO. 8011-W