

15-065-02766-00-00

Form CP-3
Rev. 6-26-62

KANSAS

TY
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8/16/67 AUG 16 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company.

Complete Address: Box #553, Russell, Kansas.

Lease Name Holley LKC Unit Well No. 204

Location NE-NW-SE Sec. 33 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3986'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Halliburton Company.

Address: Box #296, Hill City, Kansas. License No.

Operation Completed: Hour 5:45PM Day 11 Month 8 Year 1967

The Above well was plugged as follows:

216'--8 5/8" Surface pipe, cement circulated with 200 Sx.
3986'--5 1/2" Production casing cemented with 100 Sx. DV tool @ 2118' with
100 Bbl. Chempac. Tubing and rods lost in hole @ 2164', unable to fish.
Dakota section from 850' to 1050'.

Pulled 5 1/2" casing and squeezed well with 18 sacks gel and 5 sack hulls
followed with 100 Sx. cement from 1080' to 780' then 10 sacks gel from
780' to 280' and followed with 20 Sx. cement from 280' to 220', 3 Sx. gel
from 220' to 40' and 5 Sx. cement from 40' to bottom of cellar. Recovered
960' 5 1/2" casing. Maximum pump-in pressure 200#. Final shut-in Pressure 100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 8/16/67
INV. NO. 6150-W