

15-065-02740-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E. K. Carey Contractor
Complete Address: Box 620 Mc Pherson, Kansas
Lease Name Evans Well No. 2
Location SW SW SE Sec. 3 Twp. 8 Rge. (E) (W) 24
County Graham Total Depth 3763
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Bert Self
Address: Hutchinson, Kans License No. 48
Operation Completed: Hour 6PM Day 14 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 156' circulated with cement - 5 1/2" 3763' with 100 sax cement - perf 3730'

Filled with sand to 3710', set 5 sax cement with dump bailer - pulled 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (25 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced 20 sax cement through 5 1/2" - heavy mud to 35', set plug and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: E. J. Kelly
Well Plugging Supervisor

DATE 9-18-62

INV. NO. 5419-11