

15-065-02746-w-d

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Goff Well No. 4

Location SE-SE-SW ^{NE} Sec. 3 Twp. 8 Rge. (E) (W)24

County Graham Total Depth 3770

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Incorporated,

Address: Box # 22, Great Bend, Kansas. License No. 49

Operation Completed: Hour 12:30PM Day 8 Month 3 Year 1966

The Above well was plugged as follows:

155'--8 5/8" Surface pipe, cement circulated with 100 Sx.

3770'-- 5 1/2" Production casing cemented with 75 Sx. Top perforations from 3554' to 3558'.

Sanded well back to 3540 and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well with 35 sacks gel followed by 100

sacks cement. Pump-in pressure--300#. FSIP--250#. (Recovered 720'

5 1/2" casing) Mudding and cementing operations performed by Globe Oil

Well Cementing, Incorporated).

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 3/11/66
INV. NO. 2846-w