

14 KANSAS  
STATE CORPORATION COMMISSION

15-065-19078-00-00

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

5/1/62

MAY 1 1962  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Graham

Location: SW NW SE Sec. 3 Twp. 8 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 24

Name of Field: \_\_\_\_\_ Total Depth: 3806

I have this date completed supervision of plugging of:

Lease Name: Evans Well No. 3

Operator's Full Name: E. K. Carey

Complete Address: Box 620 Mc Pherson, Kansas

Plugging Contractor Bert Self

Address: Hutchinson, Kans License No. 48

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 25 Month 4 Year 62

The above well was plugged as follows:

8 5/8" 155' circulated with cement - 5 1/2" 3806' with 100 sax cement - perf  
3617' - sand to 3600', set 4 sax cement with dump bailer - pulled 100' 5 1/2"  
to 550', circulated hole with heavy mud through 5 1/2" ( 25 sax Gel), displaced  
20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced 20 sax  
cement through 5 1/2" at 170', heavy mud to 35', set bridge and cemented to bottom  
cellar.

Mudding and cementing by Halliburton Co.

Signed: Eason Peery  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED  
DATE 5/4/62  
INV. NO. 4904-2