

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 13 1962  
3-13-1962  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Graham

Location: NE NE SE Sec. 4 Twp. 8 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 24

Name of Field: \_\_\_\_\_ Total Depth: 4045

I have this date completed supervision of plugging of:

Lease Name: Neal Well No. 1

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Drawer (B) Great Bend, Kansas

Plugging Contractor R & D Casing Pulling Co

Address: Hutchinson, Kansas License No. 236

Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 8 Month 3 Year 62

The above well was plugged as follows:

8 5/8" 250' circulated with cement - 5 1/2" 3933' with 100 sax cement PB & Perf  
3581' - filled with sand to 3550', set 4 sax cement with dump bailer, pulled  
2900' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550' ( gel mud)  
displaced 20 sax cement through 5 1/2" at 550', heavy gel mud to 180', displaced  
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and cement  
to bottom cellar.

Mudding and cementing by R & D Company pump truck.

Signed: Leon Petty  
Conservation Division Agent

Reviewed: Harold Morris  
Field Supervisor

Remarks:

INVOICED  
DATE 3/19/62  
INV. NO. 4698-W