

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1962
6-19-1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: SE NE NW Sec. 10 Twp. 8 Rge. _____ (E) _____ (W) 24

Name of Field: _____ Total Depth: 3715

I have this date completed supervision of plugging of:

Lease Name: ^{KCC CAP} M.G. Goff Well No. 3

Operator's Full Name: Empire Drg Co

Complete Address: 650 4th Natl Bk Bldg Wichita, Kansas

Plugging Contractor Rocket Oil Well Service

Address: Box 7128 Denver, Colorado License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 1PM Day 16 Month 6 Year 62

The above well was plugged as follows:

8 5/8" 240' circulated with cement - 5 1/2" 3705' with 100 sax cement.

PB to 3690' - perforated 3558'

Sand back to 3540', set 4 sax cement with dump bailer - pulled 2300' 5 1/2"

to 550', circulated hole with heavy mud, displaced 20 sax cement through

5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180',

heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 6/20/62
INV. NO. 5210-W