

15-065-02748-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 28 1964  
9-28-1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Building, Wichita, Kansas.

Lease Name Goff Well No. X #2

Location CM $\frac{1}{2}$ -NE-NW Sec. 10 Twp. 8 Rge. (E) (W) 24

County Gra ham Total Depth 3706

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: 1450 Maple, Russell, Kansas. License No. 9

Operation Completed: Hour 11:30AM Day 23 Month 9 Year 1964

The Above well was plugged as follows:

150'--8 5/8" Surface pipe, cement circulated. 3705'--5 $\frac{1}{2}$ " Production casing cemented with 75 Sx. Top perforations from 3591' to 3587'.

Sanded well back to 3575' and set 5 Sx cement with dump bailer. Pulled 5 $\frac{1}{2}$ " to 600' and attempted to circulate heavy gel mud but hole would not circulate. Pulled 5 $\frac{1}{2}$ " to 500' and circulated heavy gel mud, (used 30 Sx. gel) displaced 20 Sx. cement thru 5 $\frac{1}{2}$ " @ 500'. Pulled 5 $\frac{1}{2}$ " to 150' and displaced 20 Sx. cement thru 5 $\frac{1}{2}$ ". Pulled 5 $\frac{1}{2}$ ", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. A. Nichols  
Well Plugging Supervisor

DATE 9/28/64

INV. NO. 9894-W