

15-065-30207-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1966
11-16-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Kobler Well No. E-1

Location NW-SE-NE Sec. 26 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3830

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 9:30PM Day 10 Month 11 Year 1966

The Above well was plugged as follows:

174'--8 5/8" Surface pipe, cement circulated with 125 Sx.
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.
cement thru DP. Heavy mud to 180', set plug with 1/4 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/16/66
INV. NO. 4293-11