

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Kobler Well No. F-1

Location CN/2-S/2-SE Sec. 26 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3930'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 5:00AM Day 11 Month 9 Year 1967

The Above well was plugged as follows:

173'--8 5/8" Surface pipe, cement circulated with 115 Sx.
Dakota section from 1500' to 1680'.

Circulated hole with heavy mud. Pulled DP to 1700' and displaced 100 Sx. cement thru
DP from 1700' to 1380'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set Bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

SEP 15 1967
9-15-1967

Signed: M. L. Nichol
Well Plugging Supervisor

DATE 9/15/67 CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 6336-W