

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1964
6-1-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil of Kansas.
Complete Address: Box #97, WaKeeney, Kansas.
Lease Name Kobler Well No. A-1
Location NW-SE-SW Sec. 26 Twp. 8 Rge. (E) (W) 24
County Graham Total Depth 3916
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Southwest Casing Pulling Company, Inc.,
Address: Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 10:00AM Day 26 Month 5 Year 1964

The Above well, was plugged as follows:

230' -- 8 5/8" Surface pipe, cement circulated with 150 Sx.
3915' -- 4 1/2" production casing cemented with 125 Sx. Well plugged back to
3800'. Top perforations 3745' to 3749'.

Sanded well back to 3735 and set 3 Sx. cement with dump ba iler.
pulled 4 1/2" to 660' and attempted to circulate heavy gel mud, was unable to
circulate. Pulled 4 1/2" to 500' and circulated heavy gel mud (20 Sx. gel),
and displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 210' and displaced 20
Sx. cement thru 4 1/2". Pulled 4 1/2" set bridge @ 35' and 10 Sx. cement to
bottom of cellar. (Recovered 2810' 4 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. D. Nichel
Well Plugging Supervisor

DATE 6/2/64
INV. NO. 9233-W