

15-065-20070-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8/9/67
AUG 9 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John P. Jennings,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name McFadden Estate Well No. 1

Location NE-SE-NE Sec. 23 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3615

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. _____

Operation Completed: Hour 4:15AM Day 1 Month 8 Year 1967

The Above well was plugged as follows:

161'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1300' to 1515'.

Circulated hole with heavy mud, pulled DP to 1525' and displaced 100 Sx.
cement thru DP. Pulled DP to 180' and displaced 20 Sx. cement thru DP.
pulled DP. Set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/9/67
INV. NO. 6102-W

Signed: N. S. Nichols
Well Plugging Supervisor