

15-045-20219-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1969
CONSERVATION DIVISION
Wichita, Kansas

5/12/69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tilco et al.

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name Hull Well No. 1

Location SE-NW-NW Sec. 23 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3661'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated.

Address: Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 2:15 AM Day 9 Month 5 Year 1969

The Above well was plugged as follows:

219'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru
DP from 900' to 575'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dikele
Well Plugging Supervisor

DATE 5/14/69
INV. NO. 9753-W