

15-065-01328-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

2/1/71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Barnett Oil Company,

Complete Address 411 First National Bank Building, Wichita, Kansas.

Lease Name Lyons Well No. 1

Location SE-SE-SE Sec. 2 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3798'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing, Incorporated,

Address Box #207, Russell, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 6:30 PM Day 28 Month 1 Year 1971

The above well was plugged as follows:

110'--8 5/8" Surface casing, cement circulated with 100 Sx.

3797'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3788'. Top perforations @ 3620'.

Pushed plug to 3600', sanded back from 3600' to 3575' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1020') and attempted to squeeze well. Pumped in 5 sacks hulls and 15 sacks gel and gained circulation on outside of surface casing.

On January 28, 1971 washed 2" tubing to 1000' and circulated heavy gel mud using 20 sacks gel. Pulled tubing to 970' and displaced 100 Sx. cement thru tubing from 970' to 650'. Pulled tubing to 240' and circulated cement to bottom of cellar using 75 Sx.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 2-1-71

INV. NO. 3285-11