

15-065-20073-0-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

3/17/75

MAR 17 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Hambright + Day vault
Complete Address 1415 KSB + T Bldg, Wichita Ks, 67202
Lease Name Walty Well No. 1
Location NE-NW-SW Sec. 2 Twp. 8 Rge. 24 (E) (W) X
County Graham Total Depth 3864
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling
Address Box 174 Chase Kansas License No. 683
Operation Completed: Hour 2:00 PM Day 13 Month March Year 1975

The above well was plugged as follows:

KB. 2367', Dak Top 1450, SP 125' of 8 5/8" cwc 100sx cem
4 1/2" casing 3863' w/ 150 sx cem. Plug Back To 3730'
w/ 25' sand + 3 sx cem. Perf 3764-66, 3783-85, 3796-98
1008' of 4 1/2" casing Recovered.
Pump down 8 5/8" 4 sx Hulle + 7 sx Gel
70 sx cem 50% pozmix 6% Gel + 18 sx Gel
Released Plug + 50 sx cem. 50% pozmix 6% Gel.
Closing pres 50 Lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3/20/75
INV. NO. 1018-W