

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20965-00-00
Spot: SESWNW Sec/Twnshp/Rge: 3-12S-16W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DREILING Well #: F-25
County: ELLIS Total Vertical Depth: 3399 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3400	0	w/150 sxs cmt
SURF	8.625	200	0	w/160 sxs cmt

110.47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2008 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY PIESKER Company: DREILING OIL, INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 04/25/2008 5:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:
Ran tubing to 2100' - pumped 300 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled 1000' casing - pumped 55 sxs 60/40 pozmix - 4% gel with 200# hulls - cement circulated.
Tied to 5 1/2" casing - pumped 18 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 300#. S.I.P. 300#.
Tied to 8 5/8' casing and pumped 20 sxs 60/40 pozmix - 4% gel with 50# hulls.
Hole stayed full.

Perfs:
INVOICED
DATE 5-12-08
INV. NO. 2008061707

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 06 2008
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce D. Basye
(TECHNICIAN) CM PPS

APR 28 2008

