

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25195-00-00
Spot: N2SENE Sec/Twnshp/Rge: 15-20S-14W
1550 feet from N Section Line, 660 feet from E Section Line
Lease Name: BENKER Well #: 1-15
County: BARTON Total Vertical Depth: 3750 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	806		

121.88

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/28/2008 6:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: STEVE STEVENSON Company: HOLL, F.G., COMPANY L.L.C. Phone: (316) 684-8481

Proposed Plugging Method: Ordered 170 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE
Date/Time Plugging Completed: 04/28/2008 8:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st. Plug at 3526' w/25 sxs.
2nd. Plug at 820' w/40 sxs.
3rd. Plug at 290' w/70 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 5-12-08
INV. NO. 2008061708

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: BASIC CEMENTING COMPANY-TICKET #18180.

Plugged through: DP

District: 04

Signed Darrel Dipman
(TECHNICIAN)

PKT
CM

APR 29 2008