

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-26815-00-00
Spot: SWNENE Sec/Twnshp/Rge: 26-32S-10E
1090 feet from N Section Line, 990 feet from E Section Line
Lease Name: FLOYD A Well #: 23
County: CHAUTAUQUA Total Vertical Depth: 2050 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	134		80 SX CMT.

66.63

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/24/2007 4:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: STELBAR OIL CORP. - ROS Company: _____ Phone: (316) 264-8378

Proposed Plugging Method: **PLUG WELL WITH A TOTAL OF 195 SX CEMENT AS FOLLOWS: 15 SX @ 1980', 15 SX @ 1280', 150 SX FROM 500' TO SURFACE. 15 SX IN RATHOLE. ALL CEMENT WAS 60/40 POZMIX W 4% GEL.**

Plugging Proposal Received By: STEVE KORF Witness Type: NONE
Date/Time Plugging Completed: 06/24/2007 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran pipe to 1980' and put 30 sacks (Some went into rathole). Put gel in to 1280' and put 15 sacks of cement. Put gel to 500' and cemented to surface with 150 sacks of cement. All cement was 60/40 pozmix with 4% gel. A total of 195 sacks of cement were used.

Perfs:

RECEIVED
KCC DISTRICT #3

APR 24 2008

CHANUTE, KS

DS

INVOICED
DATE 5-9-08
INV. NO. 2008061689

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 08 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Duane Sims

(TECHNICIAN)

PKT