

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
*Please TYPE Form and File ONE Copy*

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 055-00789 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Spud 2/15/1957

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334

Address: P.O. Box 18496 (Owner / Company Name) City: Oklahoma City (Operator's)

State: Oklahoma Zip Code: 73154-0496 Contact Phone: ( 405 ) 879 - 9375

Lease: McClure Well #: 1-36 Sec. 36 Twp. 23S S. R. 32  East  West

- C - NE Spot Location / QQQQ County: Finney

3960 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" 28#, J-55 Set at: 0 - 495' Cemented with: 275 Sacks

Production Casing Size: 5 1/2" 14#, J-55 Set at: 2,761' Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: Upper Krider - 2,760 - 2,678"

Elevation: 2,913 ( G.L. /  K.B.) T.D.: 2,729 P.B.T.D.: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See attached sheet.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**RECEIVED  
KANSAS CORPORATION COMMISSION**

**MAY 01 2008**

**CONSERVATION DIVISION  
WICHITA, KS**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Bud Neff, Production Superintendent Phone: ( 620 ) 277 - 0803 ext. 11

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: \_\_\_\_\_  
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, KS 67665 Phone: ( 785 ) 483 - 2627

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/30/08 Authorized Operator / Agent: Doug Henrich by Alotha Dowbre-Ries  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**Procedure:**

1. MIRU workover unit. TOOH, LD pump and rods in singles. TOOH with tubing laying down in singles.
2. MIRU wireline unit. PU setting tool, 5 1/2" CIBP, RIH and set CIBP at ±2,500'. Dump 5 sacks of cement on CIBP.
3. Load casing with fresh water. PU CBL and CCL, RIH to CIBP at ±2,500' and log back to TOC. POOH, LD CBL, PU 3 1/8" casing guns. RIH and perforate 4 way squeeze holes ±50' above TOC. POOH, RDMO wireline unit.
4. MIRU cementing services, rig up on 5 1/2" casing and attempt to establish circulation back to surface via 8 5/8" x 5 1/2" annulus. If circulation is established, mix and pump ±200 sacks of common cement, continue pumping cement until cement circulates to surface. RDMO cementing services.
5. Weld on cap and clean up location.

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 01 2008  
CONSERVATION DIVISION  
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

CHESAPEAKE OPERATING, INC.  
6200 N WESTERN AVE  
PO BOX 18496  
OKLAHOMA CITY, OK 73118-1046

May 12, 2008

Re: MCCLURE #1  
API 15-055-00789-00-00  
36-23S-32W, 1320 FNL 1320 FEL  
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after November 8, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888