

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 091-22863-00001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date \_\_\_\_\_

Well Operator: Osborn Energy, LLC KCC License #: 32294  
(Owner / Company Name) (Operator's)

Address: 24850 Farley City: Bucyrus

State: KS Zip Code: 66013 Contact Phone: ( 913 ) 533 - 9900

Lease: Tobin Well #: 1A-3 Sec. 3 Twp. 15 S. R. 24  East  West

NE - NE - NW Spot Location / QQQQ County: Johnson

4900 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2970 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 20' Cemented with: 6 Sacks

Production Casing Size: 4 1/2" Set at: 1242' Cemented with: 217 Sacks

List (ALL) Perforations and Bridgeplug Sets: 524-528, 24 shots. 561-565, 24 shots. 724-726, 8 shots. 756-760, 9 shots

Elevation: 1053 ( G.L. /  K.B.) T.D.: 1480' PBDT: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Hook up to the well and pump cement into it until it is full.

Squeeze job.

RECEIVED  
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

MAY 12 2008

If not explain why? \_\_\_\_\_  
CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Consolidated Well Services

Phone: ( 620 ) 431 - 9210

Address: 211 W. 14th Street City / State: Chanute / KS

Plugging Contractor: Osborn Energy, LLC KCC License #: 32294  
(Company Name) (Contractor's)

Address: 24850 FARLEY BUCYRUS, KS 66013 Phone: ( 913 ) 533 - 9900


Proposed Date and Hour of Plugging (if known?): May 12, 2008 9:00am

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent


Date: 5-8-2008 Authorized Operator / Agent: Custia Hamber  
(Signature)

# RIG 6 DRILLING CO.

RT. 1, BOX 132  
BRONSON, KS 66716



R.K. (Bud) SIFERS  
(316) 939-4330



JOHN J. BARKER  
(316) 365-7806

Company: Osborn Energy , LLC  
Address: 9401 Indian Creek Parkway  
Overland Park, KS 66210  
Lease: Tobin  
County: Johnson  
Location: 4900 FEL / 2970 FSL  
Sec. 3 / Twp. 15 / Rge. 24e

Commenced: 7/22/98  
Completed: 8/3/98  
Well#: 1 - A  
API#: 15-091-22,863  
Status: Gas Well

Casing: 20'- 8 5/8 surface cmt w/ 10 sx  
1241'-4 1/2 csg. w/ packer shoe, cent  
ralizers @ 1100, 700, and 240, baskets @  
975, 600.

|                          |                        |
|--------------------------|------------------------|
| 10 Soil & Clay           | 705 Sh w/ SA sh        |
| 11 Limestone (Ls)        | 707 Co & blk sh        |
| 12 Clay                  | 721 Sh                 |
| 20 Ls w/ clay            | 723 Co                 |
| 98 Ls w/ Shale (Sh) brks | 744 Sh                 |
| 110 Ls                   | 753 Sa sh              |
| 129 Sh                   | 766 Sh w/ sa sh        |
| 136 Ls                   | 770 Ls                 |
| 166 Sh                   | 811 Sa w/ sh brks      |
| 171 Ls                   | 986 Sh w/ sa sh        |
| 221 Sh                   | 1164 Ls (Miss)         |
| 224 Ls                   | 1171 Ls w/ chert       |
| 251 Sh                   | 1194 Ls                |
| 269 Ls                   | 1201 Ls w/ sa sh       |
| 290 Ls w/ sh brks        | 1447 Ls                |
| 478 Sh w/ ls brks        | 1480 Sa (Simpson) T.D. |
| 505 Ls                   |                        |
| 518 Sh                   |                        |
| 521 Ls                   |                        |
| 522 Sh                   |                        |
| 523 Co                   |                        |
| 535 Sh w/ sa sh          |                        |
| 583 Sh w/ Ls strks       |                        |

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 12 2008

CONSERVATION DIVISION  
WICHITA, KS

PAID  
CHECK NO. 2506  
AMOUNT 15135  
DATE 8/5/98

# KANSAS

## CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

OSBORN ENERGY, L.L.C.  
24850 FARLEY  
BUCYRUS, KS 66013-9264

May 13, 2008

Re: TOBIN #1A-3  
API 15-091-22863-00-01  
3-15S-24E, 4900 FSL 2970 FEL  
JOHNSON COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after November 9, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,



Steve Bond

Production Department Supervisor

District: #3  
1500 W. 7th  
Chanute, KS 67220  
(620) 432-2300