

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM

County. Sec. 3 Twp. 8 Rge. 24 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. SW NW SE.

Lease Owner E. K. CAREY CONTRACTOR.

Lease Name Evans Well No. 3

Office Address BOX 620 McPHERSON KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY

Date well completed 8-15-55 19

Application for plugging filed 3-15-62 19

Application for plugging approved 3-17-62 19

Plugging commenced April 15 19 62

Plugging completed April 24 19 62

Reason for abandonment of well or producing formation not enough to produce


If a producing well is abandoned, date of last production 3-15-62 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation L.N. K.C. Depth to top 3571 Bottom 3807 Total Depth of Well 3807 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				85/8	155	none
				51/2	3806	995.20

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back in the hole and dumped 5 sacks of cement. Shot pipe off at 995. Pulled pipe and mudded hole with Halliburton. Dumped 20 sacks of cement after rock bridge at 500'. Mudded to 170' and dumped 20 more sacks of cement. ~~XXXXXXXXXXXXXXXXXXXX~~ Finished mudding hole and dumped 10 sacks of cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 7 1962

CONSERVATION DIVISION
Wichita, Kansas

S/7/62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address RR#4 Hutchinson Kansas

STATE OF Kans. COUNTY OF Reno, ss. Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Bert Self

R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of April, 1962

My commission expires October 18, 1965

Dorothy Lee
Notary Public.

15-060-19098-00-00

NOTARY PUBLIC, KANSAS

E. F. Carey, Contractor
Box 320
Lebanon, Kansas
Ivory 13

Elevations: 2337 M.F.
2334 M.F.
2332 M.F.

3-5/8" x 6" Head 6.45'
below K. 1.

Approx. S. 31 N. W. 32 E
Sec. 3-3-24
Graham County, Kansas

Casing Record:

3-5/8" 155' w/65 sbs
Bulk Cement and 100' cc

Well Commenced: 7-13-55
Well Completed: 7-29-55

3-1/2" 3809' w/100 sbs
Pozzix Cement

Contractor: E. F. Carey, Contractor, Box 320, Lebanon, Kansas
Geologist: Tom Kollar, E. F. Carey Eng. Co. 311 Central Bldg. Wichita

Figures Indicate Bottom of Formation L. 7.

Caso and collar	2
Shale	45
Sand	50
Shale	134
Shells and shale	136
Shale and shells	200
Sand, shale and lime	1300
Shale and shells	1540
Sand	1730
Shale and shells	1900
Shale	1970
Anhydrite	1990
Lime and shale	2030
Shale and lime	2220
Lime and shale	2330
Lime and shale	2530
Lime	2735
Lime and shale	2940
Lime	3130
Lime and shale	3330
Lime	3305
Shale	3310 TD

Geologist Tops:

Neober	2540
Kansas City	2571
Case M.C.	2735
Rotary Total Depth	3310

Set 3" casing 3309' or 1 foot
off bottom. Centralizers 3700,
3735, 3782, 3840 and 3805.

ST - 3603 - 32' or 30' anchor,
stream blow. Pool open 1 hour,
closed 20 m. for WP. Recovered
1200' gas, 2335' oil and 113'
water.

ST - 3722 - 60' or 50' anchor.
Pool open 1 hour, 10 m. weak blow,
but increased. Closed 20 m. for
WP. Recovered 60' gas and 30'
heavy oil out run. WP 110'

5/11/62

CONSERVATION DIVISION
Wichita, Kansas

All above measurements to be corrected back up the hole 3 feet from top
of Lansing. 3310' equals 3307 Total Depth.

This is to certify that the above information is to the best of my
knowledge true and correct.

WITNESSED AND SIGNED to before me this 30th day of July, 1955



E. F. CAREY CONTRACTOR

BY Herbert Photon G
Herbert Photon, Superintendent

[Signature]

My Commission Expires: November 13, 1956