

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 4 Twp. 8S Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines C S/2 NW/4

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name G6ff Well No. 7

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 7 1959

Application for plugging filed March 7 1959

Application for plugging approved March 7 1959


Plugging commenced March 7 1959

Plugging completed March 7 1959

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	212'	212'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 Plug at 550' with 20 sacks cement; Set No. 2 Plug at 200' with 20 sacks cement; Set No. 3 Plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1959
3-26-1959
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Raymond L. Bacon (employee of ~~Kansas~~) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: [Signature] VpP.

780 Fourth National Bldg., Wichita 2, Kansas (Address)

Subscribed and sworn to before me this 23rd day of March, 1959

My commission expires July 7, 1962
Mona L. Latier Notary Public.



PLUGGING
FILE SEC. 4 T. 8 R. 24w
BOOK PAGE 23 LINE 39

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3-26-1959
MAR 26 1959
CONSERVATION DIVISION
Wichita, Kansas

Goff No. 7
C S/2 NW/4 Sec. 4-8S-24W
Graham County, Kansas.

Total Depth: 3900'

Commenced: 2-28-59 Completed: 3-7-59

Elevation: 2427' RB
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 212' with 165 sacks cement.

Figures indicate bottom of formations:

Surface Clay & Sand	218'
Shale	400'
Shale - Sand & Shells	1500'
Shale & Shells	1650'
Dakota Sand	1835'
Shale & Red Beds	2084'
Anhydrite	2120'
Shale & Shells	2655'
Shale & Lime	3525'
Lime	3900'
Total Depth	3900'

TOPS

Anhydrite	2084'	(/ 343)
Heebner	3651'	(-1224)
Toronto	3673'	(-1246)
Lansing	3688'	(-1261)
Rotary Total Depth	3900'	(-1473)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: A. Bacon
Vice-President

Subscribed and sworn to before me this 23rd day of March, 1959.

My Commission Expires:

July 27, 1962

Mona S. Kuter
Notary Public

PLUGGING
FILE SEC. 4 T. 8 R. 24W
BOOK PAGE 23 LINE 39