

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FORM 10
Rev. 12-15-80
APR 21 1982
4-21-1982
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 4 TWP. 8S RGE. 24 XX/W
Location as in quarters or footage from lines:
SE SE SE

Locate Well
correctly on above
Section Platt.

Lease Owner David U. Goff offord Exploration Co.
Lease Name Goff Well No. 4-164
Office Address 1550 Denver Club Building Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): dry hole
Date Well Completed June 27, 1981
Application for plugging filed July 14, 1981
Plugging commenced 10:00 AM 3-26-82
Plugging completed 1:00 P.M. 3-26-82
Reason for abandonment of well or producing formation
Not commercially productive
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation LANSING K.C. Depth to top 3656' bottom 3659' T.D. 3809'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>LANSING K.C.</u>		<u>3656</u>	<u>3659</u>	<u>4 1/2"</u>	<u>3809'</u>	<u>785'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. P.B. 3670

125' OF SAND OVER PERK. 5 SKS. CEMENT. Pull stretch & work pipe & shoot off & lay down 785' 4 1/2" pipe

3-26-82
1 mix 4 SKS. Hulls & 8 SKS. gel 70 SKS. CEMENT 5% SO Poz. 4 1/2" Gel
3% C.C. 1 SKS. gel 10 SKS. cement squeezed @ 2000 PSI

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____


STATE OF KANSAS COUNTY OF Graham, ss.

WARREN MARTIN (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren Martin
Bartholomew, Neb.
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of Apr, 19 82

My Commission expires:



Mary Ann Carney
Notary Public.

15-065-21426-00-00

WELL LOG

COMPANY Oxford Exploration

SEC. 4 T. 8S R. 24W
LOC. SE SE SE

FARM Goff

NO. 4-164


RIG. NO. 21

TOTAL DEPTH 3800'

COUNTY Graham
KANSAS

COMM. 5-23-81

COMP. 5-30-81



CONTRACTOR Murfin Drilling Company

CASING

20
15
12
13

10
8-5/8" csg. set @ 209' w/180 sx. Common Sunset
4 1/2" csg. set @ 3802' w/25 sx. Common + 100 sx. 50-50 Posmix, 2% gel,
18% salt, 75% CFR-2.

FIGURES INDICATE BOTTOM OF FORMATIONS

45'	surface sand & sand stone
210'	shale
1528'	sand & shale
1715'	Cedar Hill Sands
1967'	sand & shale
2001'	anhydrite
3070'	shale
3800'	lime & shale & RTD.

RECEIVED
STATE CORPORATION COMMISSION
4-14-1982
APR 14 1982
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK } ss:

I, David L. Murfin, Drlg. Mgr. of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Goff #4-164 well.

Subscribed and sworn to before me this 5th day of June 1981

David L. Murfin, Drilling Manager

My Commission Expires

12-19-84
LAUREL GRADERT
NOTARY PUBLIC
STATE OF KANSAS
My Appl Exp.

Laurel Gradert
Laurel Gradert NOTARY PUBLIC