

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-59757-00-00

Well was completed on: 11-22-1965
API NUMBER 11-22-1965

LEASE NAME Nana NW Unit

WELL NUMBER 308D

4980 Ft. from S Section Line

110 Ft. from E Section Line

SEC. 5 TWP. 8S RGE. 24 (E) (W)

COUNTY Graham

Date Well Completed 11-22-1965

Plugging Commenced 7-8-1988

Plugging Completed 7-8-1988

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 26, 1988 (date)

by Mr. Carl Goodrow, District #4 (KCC District Agent's Name).

Well was completed on: 11-22-1965
Is ACO-1 filed? 11-22-1965 If not, Is well log attached? Yes

Producing Formation Cheyenne Depth to Top 1200' Bottom 1400' T.D. 1430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|------|--------|------------|
| Cheyenne | (SWD) | 1200 | 1400 | 7" | 1430' | 0 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Tied onto 7" csg. & pumped 140 sx 65/35 cmt. w/10% gel +2% Econ. & 5 sx hulls filling the csg. to surface. P&A completed. State Witness: Mr. Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Company License No.

Address Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 88

Marsha G. Wilson
Notary Public

My Commission Expires:



4-1-92

DRILLER'S LOG

COMPANY: Cities Service Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: NANA UNIT
 LOCATION: 110' from East Line and
 300' from North Line of
 Sec. 5-8S-24W, GRAHAM COUNTY, KANSAS
 COMMENCED: 11-20-65
 COMPLETED: 11-22-65

| | | |
|------|-------------|----------------------------|
| 0 | 140 | Surface clay, sand |
| 140 | 745 | Shale |
| 745 | 1145 | Shale, sand |
| 1145 | 1430 | Sand |
| | <u>1430</u> | <u>RTD - Set 7" Casing</u> |

Set 1428.55' of 7" 10V 20# used casing @ 1430' cemented with 375 sacks
 Posmi.: #1 with 4% Gel

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Nana Unit, located 110' from the East Line and 300' from the North Line, of Section 5, Township 8 South, Range 24 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 24th day of November, 1965.

Ulanda Nichols
 Ulanda Nichols

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 25 1988
 5-25-1988
 CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires: April 1, 1967