

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-22569-00-00

LEASE NAME Sanger

WELL NUMBER 1

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 7 TWP. 8S RGE. 24 (X&Xr(W))

COUNTY Graham

Date Well Completed 05-29-90

Plugging Commenced 05-30-90

Plugging Completed 05-30-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Imperial Oil Properties, Inc.

ADDRESS 212 N. Market #307, Wichita, KS 67202

PHONE#(316) 265-6977 OPERATORS LICENSE NO. 03869

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05-30-90 (date)

by Gilbert Balthazor (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	208	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pump heavy mud to 2080; 1st plug 2080 to 1980; 2nd plug 1200 to 800 w/100 sx; 3rd plug 210 to 50' w/40 sx; 4th plug from 40' to surface w/10 sx; 15 sxs in rathole. All cement 60/40 pozmix 6% gel, 3% CC w/1/4# Floccel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, #801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Imperial Oil Properties, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main #801, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 90

Deborah K. Ammerman  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
6-29-90  
JUN 25 1990

CONSERVATION DIVISION  
Wichita, Kansas  
Commission Expires: 3-1-92

DEBORAH K. AMMERMAN  
Notary Public - State of Kansas  
My Appt. Expires 3-1-92