

15-065-2135-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County. Sec. 8 Twp. 8S Rge. 24 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C NW SE


Lease Owner Double Eagle Exploration, Inc.
Lease Name Goff Well No. #1
Office Address Century Plaza Bldg. - Suite 512, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 10-22-80 19
Application for plugging filed 10-22-80 19
Application for plugging approved 10-22-80 19
Plugging commenced 10-22-80 19
Plugging completed 10-22-80 19

Reason for abandonment of well or producing formation
Commercial quantities of oil not found
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3752'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	243'	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 1000' w/70 sx.
Plug @ 240' w/20 sx.
Plug @ 40' w/10 sx.
Rat Hole 5 sx.

RECEIVED 11-5-80
STATE CORPORATION COMMISSION
NOV - 5 1980
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of October, 19 80



My commission expires 10-4-83
Juanita M. Green
Notary Public.

DRILLER'S LOG

15-065-21315-00-00

COMPANY: Double Eagle Exploration, Inc.

SEC. 8 T. 8S R. 24W

WELL NAME: Goff #1

LOC. C NW SE

COUNTY: Graham

RIG NO. #4

TOTAL DEPTH 3752'

ELEVATION

COMMENCED: 10-17-80

COMPLETED: 10-22-80

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 243' w/160 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Shale	1293
Sand	1414
Shale	1500
Shale & Sand	1844
Redbed & Shale	2058
Shale	2625
Lime & Shale	2900
Shale	3115
Lime & Shale	3620
Lime	3752
ROTARY TOTAL DEPTH	3752

RECEIVED
STATE CORPORATION COMMISSION

NOV - 5 1980

CONSERVATION DIVISION
Wichita, Kansas

11-5-80

STATE OF Kansas)

SS:

COUNTY OF Sedgwick)

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Goff #1 well.

Wilson Rains

Wilson Rains

Subscribed and sworn to before me this 24 day of October, 1980.

My Appointment Expires:

10-4-83

Juanita M. Green
Juanita M. Green

