

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-01337-B

LEASE NAME U.S. GOFF B

WELL NUMBER #1

SPOT LOCATION NE SE NW

SEC. 10 TWP. 8 RGE. 24W (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 2-16-84

Plugging Completed 3-1-84

LEASE OPERATOR Tomlinson Oil Company, Inc.
Purchased By Kelso Casing Pulling
ADDRESS RFD 2 Great Bend, Kansas 67530

PHONE (316) 792-2361 OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3708'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	197'	none
				5-1/2"	3703'	815'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3454' and ran 5 sacks cement. Shot casing @2503', 2020', 1004', 815' and pulled a total of 25 joints (815') of 5-1/2" casing.

Plugged surface with 13 gel, 3 hulls, 100 cement, 12 gel, released plug and displaced with 70 cement, 50/50 pos, 10% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1984

3-7-1984
CONSERVATION DIVISION
Wichita, Kansas

My Commission expires:



SUBSCRIBED AND SWORN TO before me this 6th day of March, 1984

Irene Hoover
Notary Public

COMPANY: DERBY OIL COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: U. S. GOFF #1 ~~B-1~~ ^{B 1 KCC ZAP}
 LOCATION: NE SE NW, SEC. 10-8-24
 GRAHAM COUNTY, KANSAS
 COMMENCED: 9-9-54
 COMPLETED: 9-20-54

0	TO	190	SURFACE HOLE
190	TO	760	SHALE
760	TO	1290	SHALE AND SAND
1290	TO	1775	SHALE AND SHELLS
1775	TO	1914	SHALE
1914	TO	1945	ANHYDRITE
1945	TO	2320	SHALE
2320	TO	2639	SHALE AND LIME
2639	TO	2770	SHALE AND SHELLS
2770	TO	2905	SHALE AND LIME
2905	TO	3080	LIME
3080	TO	3225	SHALE AND LIME
3225	TO	3490	LIME AND SHALE
3490	TO	3680	LIME
3680	TO	3691	LIME AND SHALE
3691	TO	3708	LIME
3708			R.T.O.

SET 197' OF 8-5/8" SURFACE CASING, CEMENTED WITH 115 BAGS OF CEMENT.

ELEVATION: 2262 D.F.

TOPS: ANHYDRITE 1914'; HEEBNER 3485'; L.S. K.C. 3516'; R.T.O. 3708'.

DST #1 - 3587' - 3604'
 #2 - 3640' - 3675'
 #3 - 3686' - 3691'
 #4 - 3703' - 3708'

SET 3703' - 5 1/2" CASING, CEMENTED WITH 100 BAGS OF CEMENT.

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE U. S. GOFF #1, NE SE NW, SECTION 10, TOWNSHIP 8, RANGE 24 WEST, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.


 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, NOTARY PUBLIC, WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 27TH DAY OF SEPTEMBER 1954.

MY COMMISSION EXPIRES MAY 5, 1956


 NOTARY PUBLIC

Received:

2-16-1982