

15-065-01338-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME U.S. GOFF B

WELL NUMBER #2

SPOT LOCATION SW NW NE

SEC. 10 TWP. 8 RGE. 24W (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 2-24-84

Plugging Completed 3-1-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Tomlinson Oil Company, Inc.

Purchased By Kelso Casing Pulling

ADDRESS RED #2 Great Bend, Kansas 67530

PHONE # (316) 792-2361 OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3760'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	197'	none
				5-1/2"	3755'	803'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3675' and ran 5 sacks cement. Shot casing @2810', 1017', 803' and pulled a total of 26 joints (803') of 5-1/2" casing. Plugged surface with 13 gel, 3 hulls, 100 cement, 12 gel, released plug and displaced with 70 cement, 50/50 pos, 10% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION
3-7-1984
MAR 07 1984

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 84

CONSERVATION DIVISION
Wichita, Kansas
My Commission Expires: _____

 **IRENE HOOVER**
State of Kansas
My Comm. Exp. Aug. 15, 1985

Irene Hoover
Notary Public

LOG

COMPANY: DERBY OIL COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: U. S. GOFF #~~2~~^{B 2 KCC}~~3-2~~ TAP
 LOCATION: SW NW NE, SEC. 10-8-24 GRAHAM COUNTY, KANSAS
 COMMENCED: 9/21/54
 COMPLETED: 9/30/54

0	TO	70	SHALE AND SAND
70	TO	215	SURFACE MOLE
215	TO	1000	SHALE AND SAND
1000	TO	1415	SHALE, SHELLS AND SAND
1415	TO	1950	SHALE AND SHELLS
1950	TO	1960	SHALE
1960	TO	1990	ANHYDRITE
1990	TO	2125	SHALE
2125	TO	2300	SHALE AND SHELLS
2300	TO	2425	SHALE
2425	TO	2755	SHALE AND SHELLS
2755	TO	2870	SHALE
2870	TO	3065	SHALE AND LIME
3065	TO	3130	SHALE
3130	TO	3565	SHALE AND LIME
3565	TO	3760	LIME
3760			R.T.C.

SET 197' OF 8-5/8" SURFACE CASING, CEMENTED WITH 115 SACKS OF CEMENT.

ELEVATION: 2321 D. F.
 2323 K. B.

TOPS: ANHYDRITE 1960'; HEEBNER 3533'; TORONTO 3554'; L.S. K. C. 3565'; R.T.C. 3760'.

RAN 3755' OF 5 1/2" CASING, CEMENTED WITH 100 SACKS OF CEMENT.

D.S.T. #1 - 3590 - 3617'
 #2 - 3700 - 3720'
 #3 - 3723 - 3760'

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE U. S. GOFF #2, SW NW NE, SECTION 10, TOWNSHIP 8, RANGE 24 WEST, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 8TH DAY OF OCTOBER, 1954.

MY COMMISSION EXPIRES MAY 5, 1956

Mary Heinmeier
 NOTARY PUBLIC

Received:
 2-16-1982