

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

BRXNM GRAHAM County, Sec. **10** Twp. **8** Rge. **24** (XXXXX) (W) **WEST**

Location as "NE/CNW%SW%" or footage from lines **SE/4 NE/4 NW/4**
Lease Owner **EMPIRE DRILLING COMPANY**
Lease Name **EMPIRE DRILLING CO. M.G. GOFF** Well No. **3**
Office Address **650 FOURTH NAT'L, BANK BLDG, WICHITA 2, KANSAS**
Character of Well (completed as Oil, Gas or Dry Hole) **Oil Well**
Date well completed **September 8, 1954** 19
Application for plugging filed **June, 1962** 19
Application for plugging approved **June, 1962** 19
Plugging commenced **JUNE 12** 19 **62**
Plugging completed **JUNE 16** 19 **62**
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **ELDON PETTY**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **3715** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	171'	-0-
				5 1/2"	3705'	2339'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from **3715** feet to **SURFACE** feet for each plug set.

HOLE FILLED WITH SAND FROM 3715 FT. TO 3675 FT. (40 FT.). TWO SACKS OF CEMENT PLACED ON TOP OF SAND WITH BRM DUMP BAILER. ALL PIPE PULLED, HOLE FILLED WITH MUD TO 575 FT. PUMPED 20 SAX OF CEMENT; FILLED HOLE WITH MUD TO 200 FT. HOLE CAPED WITH 10 SAX OF CEMENT TO BOTTOM OF CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1962
9-24-1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor **ROCKET OILWELL SERVICING COMPANY**
Address **BOX 4748, DENVER 7, COLORADO**


STATE OF **KANSAS**, COUNTY OF **SEDGWICK**, ss.
Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Dan J. Kornfeld*
650-4th Nat'l. Bank Bldg., Wichita 2, Kansas
(Address)

Subscribed and Sworn to before me this **20th** day of **September**, 19 **62**

My commission expires **October 21, 1962**

Lucille H. Harr
Lucille H. Harr Notary Public.



L.O.G

COMPANY: EMPIRE DRILLING COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM:
 LOCATION: SE NE NW, SEC. 10-8-24
 GRAHAM COUNTY, KANSAS
 COMMENCED: 8-31-54
 COMPLETED: 9-8-54

RECEIVED ^{KCC 2AP}
 STATE CORPORATION COMMISSION M.G. GOFF #3

SEP 24 1962
 9-24-1962
 CONSERVATION DIVISION
 Wichita, Kansas

0	TO	190	SURFACE HOLE
190	TO	1355	SHALE
1355	TO	1920	SHALE AND SHELLS
1920	TO	1928	SHALE
1928	TO	1962	ANHYDRITE
1962	TO	2045	SHALE
2045	TO	2415	SHALE AND SHELLS
2415	TO	2535	SHALE
2535	TO	2790	SHALE AND SHELLS
2790	TO	2905	SHALE
2905	TO	2990	LIME
2990	TO	3060	SHALE AND LIME
3060	TO	3165	SHALE
3165	TO	3405	SHALE AND SHELLS
3405	TO	3485	LIME AND SHALE
3485	TO	3715	LIME
3715			ReT.O.

SET 171' OF 8-5/8" SURFACE CASING, CEMENTED WITH 110 SACKS OF CEMENT.

ELEVATION: 2289 K. B.

TOPS: ANHYDRITE 1928'; HEEBNER 3490'; TORONTO 3511'; L.S. K.C. 3522'; ReT.O. 3715'.

RAN 3705' OF 5 1/2" CASING, CEMENTED WITH 75 SACKS OF CEMENT.

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE GOFF #3, SE NE NW, SECTION 10, TOWNSHIP 8, RANGE 24 WEST, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 15TH DAY OF SEPTEMBER 1954.

MY COMMISSION EXPIRES MAY 5, 1956

Mary Kummer
 NOTARY PUBLIC