


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 10 Twp. 8 Rge. 24 (E) (W)  
Location as "NE/CNW&SW" or footage from lines. CN $\frac{1}{2}$  NE NW  
Lease Owner Empire Drilling Co.  
Lease Name Goff Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced Sept. 21 19 64  
Plugging completed Sept. 23 19 64  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3706 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3706 feet to surface \_\_\_\_\_ feet for each plug set.  
Sand hole to 3570' dump 5 sacks of cement on bottom.  
Circ. mud at 600' pump 20 sacks of cement to 500' Pump 20 sacks to 150' pulled pipe out put 10 sacks on top.  
Well Completed.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1964  
10-13-1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.  
Address P.O. Box 313 Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld  
Dan J. Kornfeld  
650 Fourth Natl. Bank Bldg., Wichita 2, Kansas  
(Address)

Subscribed and sworn to before me this 8th day of October, 19 64



Lucille H. Harr  
Lucille H. Harr  
Notary Public.

LOG

COMPANY: EMPIRE DRILLING COMPANY  
 CONTRACTOR: EMPIRE DRILLING COMPANY  
 FARM: GOFF #2  
 LOCATION: C N $\frac{1}{2}$  NE NW, SEC. 10-8-24  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 8-6-54  
 COMPLETED: 8-13-54

0	TO	210	SURFACE HOLE
210	TO	725	SHALE
725	TO	1355	SHALE AND SAND
1355	TO	1915	SHALE AND SHELLS
1915	TO	1950	ANHYDRITE
1950	TO	2570	SHALE AND SHELLS
2570	TO	2870	SHALE AND LIME
2870	TO	2965	SHALE
2965	TO	3045	LIME
3045	TO	3225	LIME AND SHALE
3225	TO	3340	SHALE
3340	TO	3425	SHALE AND LIME
3425	TO	3706	LIME
3706			R.T.D.

**RECEIVED**  
 TATE CORPORATION COMMISSION  
 OCT 13 1964  
 10-13-1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

SET 197' OF 8-5/8" SURFACE CASING, CEMENTED WITH 125 SACKS OF CEMENT.


ELEVATION: 2284 K. B.

TOPS: HEEBNER 3481'; TORONTO 3501'; L.S. K.C. 3512'; R.T.D. 3706'.

RAN 3700' - 5 1/2" CASING, CEMENTED WITH 75 SACKS OF CEMENT.

C E R T I F I C A T I O N

I, DAN J. KORNFELD DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE GOFF #2, C N $\frac{1}{2}$  NE NW, SECTION 10, TOWNSHIP 8, RANGE 24, WEST, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.



*Dan J. Kornfeld*  
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 19TH DAY OF AUGUST 1954.

MY COMMISSION EXPIRES MAY 5, 1956

*Mary Weiner*  
 NOTARY PUBLIC