

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-06530356-00-00

API NUMBER 4000-434

LEASE NAME Holley

WELL NUMBER 11-6

SE Ft. from S Section Line

NE Ft. from E Section Line

SEC. 32 TWP. 8 RGE. 24 (E) or (W)

COUNTY GRAHAM

Date Well Completed 4-16-66

Plugging Commenced 5-3-91

Plugging Completed 5-3-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR V.T.I. NATURAL RESOURCES

ADDRESS 1503 VINE

PHONE#(913) 625-8360 OPERATORS LICENSE NO. 30420

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on ~~4-3-91~~ 1-16-91 (date)

by CARL GOODROW DAVID WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing Formation 3949 LKC Depth to Top 3945 Bottom 3955 T.D. 3965

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|------------|-------------|-----------|--------------|--------------|------------|
| <u>KC</u> | <u>OIL</u> | <u>3945</u> | <u>55</u> | <u>5 1/2</u> | <u>214'</u> | <u>⊗</u> |
| | | | | <u>5 1/2</u> | <u>4000'</u> | <u>⊗</u> |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

PUT 250 SKS CEMENT (60-40) DOWN PIPE & 100 SKS CEMENT DOWN BACK SIDE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIER License No. _____

Address RUSSELL KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: V.T.I. 1503 VINE


STATE OF KANSAS COUNTY OF ELLIS, ss.

Jason Dungee (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jason Dungee

(Address) 1503 VINE HAYS, KS

SUBSCRIBED AND SWORN TO before me at this _____ day of August, 19 91



My Commission Expires: _____

RECEIVED
STATE CORPORATION COMMISSION
8-20-1991
AUG 20 1991

DRILLER'S LOG

COMPANY: Texaco, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: HOLLEY UNIT TR. #11
 LOCATION: SE NE NE Sec. 32-8S-24W
 GRAHAM COUNTY, KANSAS
 COMMENCED: 4-9-66
 COMPLETED: 4-16-66

| | | |
|------|-------------|--------------------------------|
| 0 | 40 | Clay |
| 40 | 80 | Shale, Sand |
| 80 | 990 | Shale |
| 990 | 1615 | Sand, Shale |
| 1615 | 2160 | Redbed |
| 2160 | 2195 | Anhydrite |
| 2195 | 2355 | Shale |
| 2355 | 2783 | Shale, Shells |
| 2783 | 3790 | Lime, Shale |
| 3790 | 3947 | Lime |
| 3947 | 3959 | Core #1 |
| 3959 | 3978 | Core #2 |
| 3978 | 4000 | Lime |
| | <u>4000</u> | <u>RTD - Set 5 1/2" Casing</u> |

Set 8 5/8" - 20.2# used surface casing @ 314' with 200 sacks Posmix, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Holley Unit Tr. #11, located SE NE NE of Section 32, Township 8 South, Range 24 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 19th day of April, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967

RECEIVED
 COMMISSION
 8-20-1991
 AUG 20 1991

15-065-30356-00-00

FOR

TEXACO INC.—LOG OF WELL
Tulsa DIVISION

640 ACRES

| | | | | | | | |
|--|--|--|--|--|--|--|--|
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

INDICATE EXACT WELL LOCATION & LEASE BOUNDARY WITHIN SECTION

WELL Holley Unit O/A Tr-11 W#6 L. D. FILE NO. 221625
 LOC. SE NE NE SEC. 32 TWP. 8S RGE. 24W
 DIST. Wichita CO. PARISH Graham STATE Kansas
 COMM. DRLG. 4-9-66 COMP. DRLG. 4-16-66 DAYS DRLG. 8
 ROT. FROM 0 TO 4000 CABLE FROM _____ TO _____
 CONTR. OR CO. RIG NO. Leben Drilling, Inc. T. D. DRILLED 4000
 COMP. T. D. 3965 ZERO ELEV. _____ GRD. ELEV. 2449 CSG. FLG. ELEV. _____
 DATE OF FIRST PROD. 4-22-66 OFFICIAL COMP. DATE 4-29-66
 LOGS RUN Radioactivity Log

CASING RECORD

| SIZE INCHES | DEPTH FEET | WEIGHT #/FT. | GRADE | RANGE | REMARKS—QUAN. CMT., TEMP. SURV., ETC. |
|-------------|------------|--------------|-------|-------|--|
| 8-5/8 | 314 | 28# | SH | | Set & cmtd 8-5/8" csg @ 314 w/200 sxs Poz 2% CaCl ₂ . Comp 9 PM 4-9-66. Cmt. circ. |
| 5-1/2 | 3999 | 14# | | | Set & cmtd 5 1/2" csg @ 3999 w/100 sxs slt sat Poz, spotted 135 sxs gel mixed w/135 bbls lse crude oil across the Cedar Hills & Dakota intervals. Comp 4 AM 4-16-66. |

COMPLETION DATA

| | | | |
|-------------------------|---------------|--|--|
| FORMATION | Kansas City | | |
| DATE OF TEST | 4-29-66 | | |
| DEPTH OF PROD. INTERVAL | 3949-55 | | |
| INITIAL PRODUCTION: | OIL - BPD 55 | | |
| | GAS - MCF - | | |
| | WATER - BPD 5 | | |
| | GOR - | | |
| | BHP - PSI - | | |
| CORRECTED API GRAVITY | 39.8° | | |
| PRODUCING CONDITIONS | Pumping | | |
| ARTIFICIAL STIMULATION | 1250 gal CRA | | |

KUBL
TULSA
HAYS
CSO

75-24-66
 1-16-67

REMARKS

WELL HOLLEY UNIT O/A TR-11 W#6 FIELD HOLLEY AREA HAYS