

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 33 Twp. 8S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW

Lease Owner Cities Service Oil Company

Lease Name Holley LKC Unit Well No. 101W

Office Address Box 553 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Water Injection

Date well completed 2-8 1964

Application for plugging filed 5-21 1969

Application for plugging approved 5-23 1969

Plugging commenced 6-20 1969

Plugging completed 6-24 1969

Reason for abandonment of well or producing formation Non Profitable

If a producing well is abandoned, date of last production Dec. 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols Morland, Kansas

Producing formation Lansing-Kansas City Depth to top 3928 Bottom 3962 Total Depth of Well 4004 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	None
				4 1/2"	4004'	1297'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with sand to 3900' 4 sx. cement to 3852'. Shot casing at 1300'.

Pulled 40 Jts. 1297' 4 1/2" casing. Pump in 5 sx. hulls, 10 sx. gel, 10 sx.

50/50 Pozmix cement, 16 sx. gel, 25 sx. 50/50 Pozmix Cement, 4 Sx. Gel, 10

Sx. 50/50 Pozmix cement. Hole filled 200# standing pressure Complete

2:30 P.M. 6-24-69

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Co.

Address Hays, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

E. W. Peterman (employee of owner) or former operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. W. Peterman*

Box 553 Russell, Kansas 67665

(Address)

Subscribed and sworn to before me this 7th day of July, 19 69

James F. Kyger

Notary Public.

10-5-72



15-065-02213-0001

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1969
CONSERVATION DIVISION
Wichita, Kansas
5/23/69

DRILLER'S LOG

CITIES SERVICE OIL COMPANY
~~Imperial Oil of Kansas, Inc.~~
~~903 Union National Bank Bldg.~~
~~Wichita, Kansas~~

Now known as:
HOLLEY 1-KC UNIT # 101W
~~Booth No. 1.~~
NE SE NW Sec. 33-8S-24W
Graham County, Kansas

Total Depth: 4010'

Elevation: 2438' R.B.
Production: D & A

Commenced: 9-9-55 Completed: 9-19-55

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 210' W/200 sacks cement.

Figures indicate bottom of formations:

Surface Clay & Sand	210'		
Shale & Shells	330'		
Sandy, Shale & Shells	1675'		
Dakota Sand	1900'		
Shale, Shells & Red Bed	2119'		
Anhydrite	2155'	Anhydrite	2119' (/319)
Shale & Shells	2485'	Heebner	3739' (-1311)
Lime & Shale	3739'	Lansing	3777' (-1339)
Lime	4010'	Rotary Total Depth	4010' (-1572)
Total Depth	4010'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Alvin L. [Signature]
Vice-President

Subscribed and sworn to before me this 29th day of September, 1955.

My Commission Expires:
April 18, 1959

Francis E. [Signature]
Notary Public