

15-065-02232-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham

County. Sec. 33 Twp. 8S Rge. XEX 24 (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW&SW" or footage from lines NE SE NE
Lease Owner Sunray Mid-Continent Oil Company
Lease Name BLACKBIEN Well No. 4
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 29 19 55
Application for plugging filed September 29 19 55
Application for plugging approved September 30 19 55
Plugging commenced September 29 19 55
Plugging completed September 29 19 55
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3992 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	314	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud 3992' to 300'
Set 8 5/8" plug at 300' with 1/2 sax hulls, 30 sax cement
Filled with mud to 15'.
Set 8 5/8 plug with 1/2 sax hulls, 15 sax cement
Hole filled to surface.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
J. F. Dingee, Ass't Dist Supt. (~~employee of owner or (owner or operator)~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. F. Dingee
Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 19 55

My commission expires December 24, 1956

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 - 1955
CONSERVATION DIVISION
Wichita, Kansas
10/7/55
Notary Public.

PLUGGING
FILE SEC 33 T 8 R 24 W
BOOK PAGE 4 LINE 31

15-065-02232-00-00

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
October 4, 1955

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: September 19, 1955
Drilling Completed: September 29, 1955

Blackburn #4 NE/4 Sec.
33-8S-24W, Graham County,
Kansas.

DRILLERS LOG

Sand & Shells	0-90
Shale & Shells	90-900
Sand, Shale & Shells	900-1590
Sand & Shale	1590-1690
Sand	1690-1820
Sand & Shale	1820-1890
Red Bed	1890-2125
Anhydrite	2125-2160
Shale & Shells	2160-2405
Shale & Lime Broken	2405-2590
Shale & Lime	2590-2765
Lime & Shale	2765-3185
Lime	3185-3290
Lime & Shale	3290-3760
Lime	3760-3807
Lime & Shale	3807-3823
Lime	3823-3920
Lime & Shale	3920-3945
Lime	3945-3982
Lime & Shale	3982-3992
Lime	3992-3992 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Blackburn #4 NE/4 Section 33-8S-24W, Graham County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham

Notary Public

February 13, 1956

My Commission Expires

10/7/55

PLUGGING
WELL SEC 33-8-24W
BOOK PAGE 4 LINE 31