

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Well was completed on
15-065-02764-00-01

API NUMBER 9-3-55

LEASE NAME Holley Unit

WELL NUMBER 202S

330 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 33 TWP. 8S RGE. 24 ~~XXXX~~ (W)

COUNTY Graham

Date Well Completed 9-3-55

Plugging Commenced 6-12-90

Plugging Completed 6-12-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA, Inc.

ADDRESS P.O. BOX 26100, Oklahoma City, OK 73126-0100

PHONE# (405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well Water Supply

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 25, 1990 (date)

by Mr. Carl Goodrow of District #4 (KCC District Agent's Name).

Is ACO-1 filed? 9-3-55 If not, is well log attached? Yes

Producing Formation Cedar Hill Depth to Top 1800 Bottom 1850 T.D. 4010

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Cedar Hill	Water Supply	1800	1850	8 5/8"	220'	-
				5 1/2"	4010'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran in and perf. above the Anhy. at 2126. Ran 2 3/8" cmt. lined tubing to 2176' and filled the 5 1/2" csg & annulus to surf w/a total of 380 sx 65/35 cmt w/6% gel & 6 sx of hulls.

State Witness: Mr. Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. _____

Address Wichita, Kansas STATE _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA, Inc. JUL 1990

STATE OF Oklahoma COUNTY OF Oklahoma, ss. 7/3/90

Bryan Humphries (Employee of Operator) for (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Bryan Humphries

(Address) P.O. Box 26100, Oklahoma City, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 29th day of June, 1990

Kay Ann Kilmer
Notary Public

Commission Expires: 4-16-94



15-065-02764-00-01



MEMORANDUM
OCCIDENTAL OIL AND GAS

Wichita, Kansas
May 24, 1990

TO: Mr. M. D. Harrison
FROM: Mr. P. W. Pringle
SUBJECT: PLUGGING PROCEDURE.....HOLLEY UNIT #202S
330' FSL - 3300' FEL
SECTION 33-8S-24W
GRAHAM COUNTY, KANSAS

WELL DATA

8-5/8" @ 220' W/ 175 SX
5-1/2" @ 4010' W/ 125 SX
PBSD 1529'
Suspected holes @ 1364', 1390', 1420'
Cedar Hills Perfs 1800-1850'
* F.U. last measured @ 1384'

SHALLOW FORMATION DATA

Dakota 940-1230'
Cheyenne 1270-1470'
Anhydrite 2136'

1. Contact the KCC District Office #4, Mr. Dale Balthazor to obtain final approval of plugging project (913) 628-1200, Hays, Kansas.
2. Clean out fillup and drill out cement plug 1529-1538', cleaning out to 2160'.
3. Run in hole w/ gun and perf at 2126' w/ 4 SPF.
4. Run in hole w/ workstring to 2126' and spot 65/35 cement w/ total 6% gel (approx. 300 sx cement) + hulls to surface. Tie onto 5-1/2", pressure up, and attempt circulation.
5. If needed, tie onto 8-5/8" and pump 100 sx same cement down annulus to surface.
6. Let cement set 48 hours, check TOC and cap well.

PWP/cd

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1990
CONSERVATION DIVISION
Wichita, Kansas
S/24/90