

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-065-02678-00-02  
 02768  
 Well was completed on:  
 API NUMBER 11-16-55

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME Holley LKC Unit  
 WELL NUMBER 206 W  
1650 Ft. from S Section Line  
3630 Ft. from E Section Line  
 SEC. 33 TWP. 8S RGE. 24  
 COUNTY Graham  
 Date Well Completed 11-16-55  
 Plugging Commenced 8-23-1988  
 Plugging Completed 8-23-1988

LEASE OPERATOR OXY USA Inc.  
 ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100  
 PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Input  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 23, 1988 (date)  
 by Mr. Carl Goodrow of District #4 (KCC District Agent's Name).

Well was completed on:  
 Is ACO-1 filed? 11-16-55 If not, Is well log attached? Yes

Producing Formation LKC Depth to Top 3957 Bottom 3961 T.D. 4035  
3977 3979

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	(Inj.)	3957	3961	8-5/8"	225'	0
		3977	3979	5-1/2"	4035'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran in well & perf. the Anhydrite at 2146' w/4 SPF & the Dakota at 1450' w/3 SPT. Tied onto the 5-1/2" csg. & pumped 425 sx 60/40 cmt. w/8% gel + 300# hulls to surface. Tied onto the 8-5/8" csg. & filled to surface w/100 sx 60/40 cmt. w/8% gel + 100# hulls.  
P&A completed. State Witness: Mr. Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Company License No. \_\_\_\_\_

Address Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.


STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 12 1988  
 SUBSCRIPTION DIVISION  
 CONSOLIDATED AND SWORN TO  
 WICHITA, KANSAS

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100



sworn to before me this: 8th day of September, 19 88

Marsha E. Wilson  
 Notary Public

My Commission Expires: \_\_\_\_\_