

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL FLUGGING RECORD
K.A.R.-82-3-117

15-065-02774-00-02
Well was completed on:
API NUMBER 12-26-56

LEASE NAME Holley LKC Unit

WELL NUMBER 209W

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 33 TWP. 8S RGE. 24 W

COUNTY Graham

Date Well Completed 12-26-56

Plugging Commenced 8-23-88

Plugging Completed 8-23-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 23, 1988 (date)

by Mr. Carl Goodrow of District #4 (KCC District Agent's Name).

Is ACO-1 filed? Well was completed on: 12-26-56 If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3938 Bottom 3864 T.D. 3972'
3917

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	(Inj.)	3938	3942	8-5/8"	150'	
		3864	3870	5-1/2"	3998'	
		3917	--			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran in well & perf. the Anhydrite at 2140' w/4 SPF & the Dakota at 1450' w/3 SPT. Tied onto the 5-1/2" csg. & pumped 420 sx 60/40 cmt. w/8% gel + 300# hulls to surface. Tied onto the 8-5/8" csg. & filled to surface w/100 sx 60/40 cmt. w/8% gel + 100# hulls.
P&A completed. State Witness: Mr. Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Company License No. _____

Address Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

Subscribed and sworn to before me this 8th day of September, 19 88

Marsha G. Wilson
Notary Public

My Commission Expires: 4-1-92

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1988

CONSERVATION DIVISION
Wichita, Kansas

