


15-065-00914-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County, Sec. 35 Twp. 8 Rge. (E) 24 (W)

Location as "NE/CNWxSWx" or footage from lines SW SW SW
Lease Owner Francis Oil & Gas, Inc.
Lease Name Keith D Well No. 1
Office Address 905 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed July 19 19 56
Application for plugging filed July 19 19 56
Application for plugging approved July 19 19 56
Plugging commenced July 19 19 56
Plugging completed July 19 19 56
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3980 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	201	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY ROTARY MUD TO 190 FT.,
SET PLUG AND CEMENTED WITH 15 SACKS CEMENT
AND ONE-THIRD SACKS HULLS THROUGH DRILL PIPE.
MUDDING HOLE TO 35 FT., SET PLUG AND CEMENTED WITH
10 SACKS CEMENT TO BASE OF CELLAR.

STATE CORPORATION COMMISSION

JUL 23 1956

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor H 30, Inc.
Address 710 Petroleum Bldg., Wichita, Kansas

7-28-56

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg (employee of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Sponenberg*
(Address) _____

SUBSCRIBED AND SWORN to before me this 23rd day of July, 19 56

Rose Furey
Notary Public.

My commission expires February 13, 1960

PLUGGING
FILE SEC 35 T 8 R 24W
BOOK PAGE 82 LINE 31

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-069-009114-00-00

COMPANY **Francis Oil & Gas, Inc.**

SEC. 35 T. 8S. R. 24W

LOC. SW SW SW

FARM **Keith D**

NO. 1

COUNTY **Graham**

TOTAL DEPTH **3980**

COMM. **7/9/56**


COMP. **7/18/56**

KANSAS

SHOT OR TREATED

CONTRACTOR **H 30, Inc.**

ISSUED



CASING

20	10	
15	8	201'
12	6	
13	5	

ELEVATION **2406 KB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface clay and sand	70
Shale	610
Shale & Shells	1405
Shale & Little Iron	1425
Shale & Shells	1435
Red Bed & shale	1640
D Sand	1790
Shale & Red Bed	2075
Anhydrite	2115
Shale, Shells & Red Bed	2450
Shale & Lime	3790
Kansas City Lime	3824
Lime	3905
Kansas City Lime	3950
Lime	3980

FORMATION TOPS

LANSING 3746

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *C.P. Spang*

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 23rd day of July, 1956

Rose Fusco
 Notary Public

My Commission expires February 13, 1960.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 28 1956

CONSERVATION DIVISION
 Wichita, Kansas

7-28-56

PLUGGING
 FILE SEC 35 T 8 R 24W
 BOOK PAGE 82 LINE 31