

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-20,791-00-00

LEASE NAME Newmont

WELL NUMBER 1-5

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 9 RGE. 26 (E or W)

COUNTY Sheridan

Date Well Completed 2-20-85

Plugging Commenced 2-21-85

Plugging Completed 2-21-85

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947, Pratt, Kansas 67124

PHONE# ( 316 ) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4040

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged well with 185 sxs 50/50 poz, 6% gel, 3% cc as follows: 2220'-25 sxs; 1250'-100 sxs; with 1 sx celloflake; 300'-40 sxs; 40'-10 sxs with solid bridge; rathole-10 sxs. Job by Sun Cementing. Plug down at 8:30 p.m. on February 21, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss. \_\_\_\_\_


RECEIVED  
STATE CORPORATION COMMISSION  
05-05-1985  
MAR 05 1985

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have conserved the facts, statements, and matters herein contained and the log of the above-described well filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1985



Mary L. Tjaden  
Notary Public

My Commission Expires: 3/22/88



**Oilfield Services, Inc.**

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

15-179-20791-00-00

Newmont #1-5  
 NE NE Sec. 5-9S-26W  
 Sheridan County, Kansas  
 Commenced: 2-14-85  
 Completed: 2-21-85  
 API #15-179-20,791-00-00  
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	270	Sand, Clay	Ran 6 joints (254') new 24#, 8 5/8" surface casing. Set at 264' with 175 sxs Common, 2% gel, 3% cc. Job by Sun Cement. Plug down at 7 p.m. on February 14, 1985.
270	649	Sand, Shale	
649	1959	Clay, Shale	
1959	3787	Lime, Shale	
3787	3834	Lansing	
3834	4040	Lime, Shale	
		T.D.	RTD 4040'
			Well was plugged with 185 sxs 50/50 poz, 6% gel, 3% cc as follows: 2220'-25 sxs; 1250'-100 sxs with 1 sx celloflake; 300'-40 sxs; 40'-10 sxs with solid bridge; rathole-10 sxs. Job by Sun Cement. Plug down at 8:30 p.m. on February 21, 1985. State Plugger was out of the Hays, Kansas office.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 ARNIE LITTLE, VICE-PRESIDENT

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 05 1985

*Mary L. Tjaden*  
 NOTARY PUBLIC

CONSERVATION DIVISION  
 Wichita, Kansas

My Commission Expires:

3/22/88

