

15-179-20384-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Sheridan County, Sec. 6 Twp. 9 Rge. 26W (E) (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SW SW
Lease Owner Chief Drilling Co., Inc. & P.S. Petroleum Co.
Lease Name Popp Well No. 1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5/10/74 19
Application for plugging filed 5/9/74 19
Application for plugging approved 5/9/74 19
Plugging commenced 5/10/74 19
Plugging completed 5/10/74 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation Depth to top Bottom Total Depth of Well 4015' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	243'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 1250' w/70 sacks cement.
Plugged through drill pipe @ 250' w/30 sacks cement.
Plugged through drill pipe @ 40' w/10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1974
CONSERVATION DIVISION
Wichita, Kansas
05-15-1974

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 13th day of May, 1974

My commission expires August 5, 1975
Virginia S. Fabian
Notary Public.



15-179-20384-00-00

WELL LOG

CHIEF DRILLING CO., INC. &
P. S. PETROLEUM CO.
Suite 905 Century Plaza
Wichita, Kansas 67202

POPP #1
C S/2 SW SW Sec. 6-9-26W
Sheridan County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Set 237' of 8 5/8" w/160
sacks common quick set cement

COMMENCED: 5/1/74
COMPLETED: 5/10/74

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1974
05-15-1974
CONSERVATION DIVISION
Wichita, Kansas

FORMATION	FROM	TO
Surface Hole	0	249
Shale	249	480
Shale & Sand	480	1725
Shale	1725	2217
Shale & Shells	2217	2233
Anhydrite	2233	2267
Shale & Shells	2267	2300
Shale	2300	2525
Shale & Lime	2525	2900
Lime & Shale	2900	3634
Lime	3634	4015
Total Depth	4015	

ELEVATION

2628 Gr.
2630 D.F.
2633 K.B.

ELECTRIC LOG TOPS

Anhydrite	2233 +	400
Base Anhy.	2267 +	366
Heebner	3733 -	1100
Toronto	3755 -	1122
Lansing	3773 -	1140
B.K.C.	3995 -	1362
L.T.D.	4015 -	1382

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C S/2 SW SW of Section 6-9-26W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson

Jim Robinson, Vice President

Subscribed and sworn to before me this 13th day of May, 1974.

Virginia S. Fabian

Virginia S. Fabian, Notary Public

MY COMMISSION EXPIRES:

August 15, 1975

