

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20,811-00-00

LEASE NAME Minium

WELL NUMBER 1

SPOT LOCATION SW SE NE

SEC. 8 TWP. 9S RGE. 26 (E) or (W)

COUNTY Sheridan

Date Well Completed 5-11-85

Plugging Commenced 5-11-85

Plugging Completed 5-11-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Viking Resources

ADDRESS 217 E. Williams, Wichita, KS 67202

PHONE # 316, 262-2502 OPERATORS LICENSE NO. 5011

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size 8 5/8	Put in 256	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

- Spotted 20 sx @ 2250' thru -rill pipe
- 100 sx @ 1350'
- 40 sx @ 300'
- 10 sx @ 40'
- 15 sx @ in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420
Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernest Sifford


(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202


before me this 16th day of May, 1985

David F. Jamis
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
05-20-1985
MAY 20 1985

My Commission expires: _____
CONSERVATION DIVISION
Wichita, Kansas





15-179-20811-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Viking Resources
217 E. Williams
Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Minium Well No. 1

Sec. 8 T. 9S R. 26W Spot SW SE NE

County Sheridan State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 256' with 2% gel
3% cc 185 sx.
Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4040'

Drilling Commenced 5-4-85 Drilling Completed 5-11-85

Formation	From	To	Tops
Cellar	0	7	Anhydrite -2220
Shale, Sand	7	260	K. C. -3711
Shale	260	400	
Shale, Sand	400	2220	
Shale, Lime	2220	3105	
Lime	3105	3525	
Shale, Lime	3525	3711	
Lime	3711	4040	

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1985
05-20-1985
CONSERVATION DIVISION
Wichita, Kansas